

BIDDER QUESTION RESPONSE

December 15, 2016

PROJECT: Port of Kingston – Covered Moorage Roof Replacement

This question response forms a part of the Contract Documents and modifies the original Quote Requirements dated November 16, 2016 as noted below. Acknowledge receipt of this questions response in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

This Question Response **does not** change the bid opening date or time.

1. Bidder Question: Please provide clarification to the spacing and location of track for bird deterrence system as noted in Specification 10 81 13.

Response: Specification 10 81 13, Part 3, Section 3.3.A shall be replaced with the following:

- A. Install system as recommended by the manufacturer. Utilize adhesive or non roof penetrating connectors to anchor device securely to architectural surfacing.
 1. The Device shall be installed along the perimeter of each roof structure of each dock, C-, D- & E- (eaves, gables and ridge); 6 total roof structures. Additionally, the device shall be placed linearly along the long axis of each roof structure on each dock creating 3 equal bays between the eave and ridge. Intermediate stips of the device creating the 3 equal bays shall be oriented in the same direction as the open web steel joists.
 2. The device at the perimeter of the roof shall be placed within 8 inches of the edge of the roof.
 3. The device shall be installed straight, or follow the contours of the architecture.

2. Bidder Question: Please provide contact information for bird deterrence system provider, Orkin Pest Control.

Response: Provider contact is Shane Klevin of Orkin Pest Control.

END OF BIDDER QUESTION RESPONSE